

### EPA Grant-Funded Sidestream Nutrient Removal Study



**Presentation to BACWA Board Meeting** 

September 26, 2014

### **Outline**



- Overview of EPA grant-funded Sidestream Nutrient Removal Study
- Update on pilot testing of sidestream treatment technologies
- Planned next steps



### **EPA Project Overview**

Focus on Sidestream Nitrogen Removal

### **Main Tasks**

- Identify cost-effective nutrient removal technologies for sidestream treatment through literature review and bench/pilot testing at multiple sites
- Quantify potential nutrient load reductions and estimate cost-benefit (\$/Ib N removal)
- Utilize SFEI's simulation model to demonstrate water quality improvement to the Bay, assuming full-scale implementation of sidestream treatment by POTWs
- Evaluate the role of sidestream treatment in the development of a regional approach to nutrient management





# Update on Pilot Testing of Sidestream Treatment Technologies

# Bench and Pilot Testing by POTWs



### **EBMUD**:

### **Anammox**

- Suspended -growth
- Attachedgrowth


### **Ongoing**

### **SFPUC:**

### **Anammox**

- Suspended -growth
- Attachedgrowth
- Biozeolite

Operated for 3-5 months



DD: CANDO Schedule extended

OLSD: Zeolite anammox Started

USD: Krüger ANITA™ Mox Completed

### Pilot Testing Objectives



### **Pilot Test Objectives**

## Evaluate cost-effective sidestream treatment technologies on:

- Applicability for treating sidestreams with various characteristics
- Optimal process control & operational parameters
- Process performance and comparison
- Feasibility of growing anammox bacteria from activated sludge

Which technology?
What %N removal?

### **Data Usage**

To quantify potential nutrient load reductions for costbenefit (\$/lb N removal) analysis of sidestream treatment by POTWs.



# Typical Sidestream Characteristics for ANITA<sup>™</sup> Mox



### Typical Sidestream Characteristics

\*The values below are typical evaluated sidestream characteristics. Values outside these ranges could result in an increased or decreased removal rate and can be evaluated on a project by project basis.

| Temperature, °C   | 20-35*     |
|---|------------|
| Ammonia-N, mg/L   | 200-2,000* |
| sbCOD/N ratio   | <1*        |
| TSS, mg/L   | < 2,000*   |
| Ratio of Alkalinity, mg/L to $NH_4$ -N, mg/L removed $CaCO_3$ : $NH_4$ -N removed | >4*        |

Source: Krüger (October 2014)

### Pilot Testing Data Collection



|                                | Variables   |  |
|--------------------------------|---|--|
| Key sidestream characteristics | Ammonia-N concentration                           |  |
|                                | Alkalinity/N ratio                                |  |
|                                | Temperature                                       |  |
|                                | Total and soluble COD                             |  |
|                                | TSS   |  |
| Process control strategy       | pH range  |  |
|                                | DO range  |  |
|                                | Temperature                                       |  |
| Process performance            | Specific ammonia loading rate                     |  |
|                                | Ammonia and Inorganic Nitrogen removal efficiency |  |
|                                | Chemical usage                                    |  |
|                                | Process stability                                 |  |
|                                | Energy consumption                                |  |




# To-date Pilot Testing Results

# Delta Diablo CANDO Pilot Testing Update


9/22/2014



### Completed Bench-Scale Demonstration










### **CANDO Pilot Testing Goals**


(1) Achieve at least same N-balance as bench-top test



75% Conversion to N<sub>2</sub>O 95% N-Removal

(2) Maximize P-recovery?

(3) Use fermented biosolids for carbon



# SFPUC Sidestream Nitrogen Removal Study




..

### **Overview**



- Suspended-growth
- Attached-growth
- Biozeolite

### Two-phased project:



### **Reactor Data**

| Reactor   | Suspended-<br>growth               | Attached-<br>growth                                     | Biozeolite                  |
|---|------------------------------------|---|-----------------------------|
| Volume  | 24-gallon                          | 24-gallon   | 24-gallon                   |
| Reactor operation   | SBR<br>fill-hold-draw<br>operation | MBBR<br>semi- or<br>continuous flow                     | semi- or<br>continuous flow |
| Carrier (media)   | None                               | Kaldnes plastic<br>media (filled 50%<br>reactor volume) | 3/4" diameter<br>Zeolite    |
| Target NH <sub>4</sub> +-N loading rate for Period 1 (kg NH <sub>4</sub> +-N/m <sup>3</sup> /d) | 0.5                                | 0.8   | 1.0                         |

### Simplistic control strategy utilizing a PLC to monitor and control:

- -Dissolved oxygen levels
- -Airflow
- -Feed Flow/Level
- -Aerobic/anoxic periods
- -Recirculation/Mixing

# **Pilot Setup**

Page 18

### **Summary**

| Reactor Performance  |  |   |                                  |                           |  |  |
|----------------------|--|---|----------------------------------|---------------------------|--|--|
| Anammox<br>Process   | Target Loading<br>(kg NH <sub>4</sub> +-<br>N/m <sup>3</sup> /d) | Current Loading<br>(kg NH <sub>4</sub> +-<br>N/m <sup>3</sup> /d) | Ammonia<br>Removal<br>Efficiency | TIN Removal<br>Efficiency |  |  |
| Suspended-<br>growth | 0.5  | 0.2   | 67%                              | 62%                       |  |  |
| Attached-<br>growth  | 0.8  | 0.13  | 63%                              | 63%                       |  |  |
| Biozeolite           | 1.0  | 0.6   | 69%                              | 68%                       |  |  |

### Next Steps:

- Increase to target ammonia loads by the end of 2014
- Achieve >90% ammonia removal and >75% TIN removal

### EBMUD PRESENTATION 09/22/14

# ZEOLITE ANAMMOX DE-AMMONIFICATION PROCESS

ORO LOMA SANITARY DISTRICT

Jimmy Dang, P.E.

Rob Collison, P.E.

### <u>INTRODUCTION</u>

- Zeolite-anammox is a fixed film bioreactor
- Zeolite aggregate graded from 0.25" to 1" sized aggregate media
- Pilot plant of six 55-gallon drums
- ◆ Currently running transitional system 20,000-gallon baker tank treating 10% of side-stream flow
- Aeration by re-circulating trickling filter

### PILOT PLANT


◆ Commissioned November 2012, ended June 2014

Very fast anammox establishment (7)

weeks)



### PILOT PLANT



- ♦ Influent 500 mg/L NH<sub>4</sub>+-N
- ◆ Effluent 100 mg/L NH<sub>4</sub>+-N; 100 mg/L NO<sub>3</sub>--N
- ♦ 80% NH<sub>4</sub>+-N removal, 60% TIN removal
- 0.35 kg/m³/day NH<sub>4</sub>+-N removal (~0.44 kg/m³/day NH<sub>4</sub>+-N loading rate)

### TRANSITIONAL SYSTEM

- ◆ Volume 20,000 gallons
- → Flow 10 gpm
- ◆ Re-circ. 50 gpm
- Teething troubles
- Total cost: \$70K
   (design,
   construction,
   materials)



### TRANSITIONAL SYSTEM



### **NEXT STEPS**

- Build filter to remove TSS
- Nitrifier establishment period
- Anammox establishment period
- Monitor TSS levels, biofilm thickness, and porosity of system

### Union Sanitary District Anitamox Sidestream Pilot Study

Tim Grillo, R&S Team Coach

EPA Sidestream Nutrient Removal Study Workshop 2 EBMUD September 22, 2014

### Study Objectives

To determine whether sidestream treatment using the Kruger Anitamox (MBBR) is a viable alternative for reducing the ammonium in the USD treatment plant effluent.

 Determine whether a full scale implementation is feasible for USD

 Determine whether centrate dilution will be an effective struvite control strategy

### Study Phases

- Phase I To evaluate process parameters for the continuous feed with undiluted centrate
- Phase II To evaluate process parameters for the intermittent feed with undiluted centrate
- Phase III To evaluate process parameters for the continuous feed with diluted centrate
- Phase IV To evaluate Process Parameters for the intermittent feed with diluted centrate

### **Project Progress**

- Field testing is completed
- The pilot plant had been demobilized and returned to Krüger
- Data validation and reduction has begun
- Krüger has agreed to provide a conceptual design of alternatives for full scale projects.

### Preliminary results

- Preliminary results indicate that sidestream treatment with the Anitamox MBBR is a viable alternative for reducing ammonium in Union Sanitary District treatment plant effluent
- Preliminary results indicate that centrate dilution will not be a useful method to control struvite in a full scale system
- Krüger's conceptual design will help us to determine whether a full scale system can meet site constraints
- Interesting results for nitrate production during intermittent feeding – may need further consideration.

### Questions?





# EBMUD Anammox Pilot Testing Update




### **Anammox Pilot Test Goals**



- Test feasibility of anammox in treating high ammonia centrate (~2,000 mg/L)
- Grow anammox bacteria from activated sludge
- Compare two anammox processes side-by-side
- Evaluate impacts of operational and control parameters

### Reactor 2: Attached-growth

(260-gallon moving bed biofilm reactor MBBR)



### Reactor 1: Suspendedgrowth

(260-gallon sequencing batch reactor SBR)

### **Anammox Pilot Testing**





Reactor 2: Attached-growth (Started in September 2013, with NO anammox seed)

### Reactor 1: Suspended-growth

(Started in June for nitritation first, then July 2013 for anammox with 1-gal anammox seed from HRSD)



Added 1-gal anammox seed to 260-gallon reactor



### **Anammox Pilot Results To Date**



- Anammox population was growing till the process upsets occurred at the end of June 2014
  - We have been able to increase ammonia loading to more than 0.4 (suspended-growth) and 0.6 (attached-growth) kg NH<sub>4</sub>+-N/m<sup>3</sup>-reactor/day, while still achieving more than 90% ammonia-N removal.
- Activated sludge can be used as the seed to start an anammox reactor



### Next Steps for EPA Project

### **Next Steps**





- Coordinate pilot testing [EBMUD/POTWs]
- Finalize Sidestream Data Questionnaire and start data collection [HDR/BACWA/EBMUD]
- Prepare for next Team Workshop and EPA Progress Review Meeting [EBMUD/Team]
- Finalize literature review report [HDR]
- Develop Scope of Work for EBMUD/ReNUWIt contract [EBMUD/ReNUWIt]



### **Questions/Comments**

**Contact** 

**Donald Gray** 

dgabb@ebmud.com

Or Yun Shang

yshang@ebmud.com

