





Palo Alto Regional Water Quality Control Plant Secondary Treatment Upgrades



CITY OF
**PALO
ALTO**

August 29, 2024



Agenda

1. Palo Alto RWQCP Factoids
2. Project Drivers
3. Process Selection
4. Construction Update
5. Project Team, Costs, and Timeline

Agenda


1. Palo Alto RWQCP Factoids
2. Project Drivers
3. Process Selection
4. Construction Update
5. Project Team, Costs, and Timeline

Existing secondary treatment: FFR + NAS



Existing secondary process design criteria

| Parameter | Value |
|-----------------------------|--|
| Fixed Film Reactors | |
| Number | 2 |
| Diameter, each | 95 ft |
| Media Depth | 21.5 ft |
| Aeration Tanks | |
| Number/Type | 4 Complete Mix (Fine Bubble) Aerators |
| Side Water Depth | 16.25 ft |
| Volume, each | 1.98 Mgal |
| Secondary Clarifiers | |
| Number | 4 square, 2 circular |
| Plan Dimensions | 120 ft x 120 ft (square) 120 ft diameter (circular) |



Agenda

1. Palo Alto RWQCP Factoids
2. Project Drivers
3. Process Selection
4. Construction Update
5. Project Team, Costs, and Timeline

Project driver: Aging infrastructure


Aeration Blower (1980)




Fixed Film Reactors (1980)
Intermediate Lift Pumps (1988)



Project driver: Planned growth in service area



Project driver: Limits on nitrogen to San Francisco Bay



Second Nutrient Watershed Permit Target = 3,000 kg/d (Existing Performance + 15%)

New 2034 Load Target
Capacity limitations prevents construction of MLE in existing tanks

Agenda

1. Palo Alto RWQCP Factoids
2. Project Drivers
3. **Process Selection**
4. Construction Update
5. Project Team, Costs, and Timeline

Re-evaluation of secondary treatment alternatives


| Parameter | Alternative 1A Convention MLE Activated Sludge | Alternative 1B Convention Step-feed Activated Sludge | Alternative 2 Step-feed Activated Sludge + MABR Intensification |
|-----------------------------------|--|--|--|
| Additional tankage requirement | ✘ | ✘ | ✓ |
| Ability to conduct maintenance | ✘ | ✓ | ✓ |
| Ability to achieve ammonia limits | ✘ | ✓ | ✓ |
| Ability to achieve TIN target | ✘ | ✓ | ✓ |
| Ability to phase implementation | ✘ | ✘ | ✓ |

✓: Superior performance


✘: Inferior performance

Retained for further evaluation

Project driver: Limits on nitrogen to San Francisco Bay



Alternative 1 – Conventional step-feed AS process flow diagram



Added Scope for Alt 1

Base project. Must be constructed with added scope items (i.e., cannot be phased)

Legend:

Normal Operation (3-Step Feed Mode) ———

High-Flow Operation (Contact Stabilization Mode) - - - - -

AER Aerobic
 ANX Anoxic
 ML Mixed Liquor

PE Primary Effluent
 RAS Return Activated Sludge
 SE Secondary Effluent
 WAS Waste Activated Sludge

Alternative 1 – Conventional step-feed AS site layout


Conflict with
2 x 96" pipes

New first stage
aeration tanks


New ML
distribution
structure

PE lift station

Mods to existing
aeration tanks
not shown



Alternative 2- Step-feed AS + MABR Intensification



Base Project
(shaded)

Legend:

Normal Operation (3-Step Feed Mode)

High-Flow Operation (Contact Stabilization Mode)




AER Aerobic
ANX Anoxic
ML Mixed Liquor

PE Primary Effluent
RAS Return Activated Sludge
SE Secondary Effluent
WAS Waste Activated Sludge

Alternative 2

Step-feed AS + MABR intensification



MABR example installation at Yorkville-Bristol San District



before




after


MABR Cassette Version 2.0 versus 2.0+

| Parameter | V2.0 | V2.0+ | Difference, % |
|--|-------|-------|---------------|
| # modules per cassette | 48 | 52 | +8% |
| Module surface area per cassette, m ² | 40 | 45 | +12.5% |
| Surface area per cassette m ² | 1,920 | 2,340 | +21% |
| Avg airflow per cassette, scfm | 5 | 6 | +20% |
| Max airflow per cassette, scfm | 10 | 12 | +20% |

Weighted non-monetary benefits favor MABR-AS



Benefit-to-cost ratio (“bang for the buck”) favors MABR-AS





AT Influent Channel

Load Center 11

Fixed Film Reactors

Tertiary Filters

Intermediate Lift Station

RAS PS 1

Primary Sedimentation Tanks

Secondary Clarifier 5

RAS PS 2


Blower Room

Secondary Clarifier 6


Equipment Room

Standby Generator


Secondary Clarifiers 1-4






Aeration Tank 1



Anoxic Zone 3 with MABR cassettes



Large-bubble mixing in unaerated zones and structures



A Lot of Temporary Systems Needed for Construction

6 temporary bypass pumping systems
 + temporary blower system
 + temporary standby generator

| PARAMETER | SYSTEM 1 | SYSTEM 2A | SYSTEM 2B | SYSTEM 2C | SYSTEM 2D | SYSTEM 3 |
|---|--|--|--|--|--|--|
| FLUID | PE | ML | ML | ML | ML | PE |
| CONSTRUCTION PHASE | 05 | 01 | 02 | 03 | 04 | 06 |
| SOURCE OF FLOW | Primary Effluent Channel | Aeration Tank 3 | Aeration Tank Influent Channel | Aeration Tank 1 | Aeration Tank Influent Channel | Fixed Film Reactors Effluent Channel |
| DESTINATION OF FLOW | Two new elevated aeration tank influent channels, flow split evenly between the two channels | Aeration Tank Effluent Structure | Aeration Tank 4 | Aeration Tank Effluent Structure | Aeration Tank 2 | Influent Channel of Primary Sedimentation Tanks |
| MINIMUM NUMBER OF PUMPS | 7 duty and 1 standby | 3 duty and 1 standby | 3 duty and 1 standby | 3 duty and 1 standby | 3 duty and 1 standby | 1 duty and 0 standby |
| MINIMUM FLOW CAPACITY OF ALL DUTY PUMPS COMBINED | 55,600 gpm | 26,700 gpm | 26,700 gpm | 26,700 gpm | 26,700 gpm | 1,000 gpm |
| MINIMUM HEAD CAPACITY | To be determined by temporary system design engineer | To be determined by temporary system design engineer | To be determined by temporary system design engineer | To be determined by temporary system design engineer | To be determined by temporary system design engineer | To be determined by temporary system design engineer |
| PREREQUISITES FOR REMOVAL OF TEMPORARY PUMPING SYSTEM | See Section 01 12 16 | See Section 01 12 16 | See Section 01 12 16 | See Section 01 12 16 | See Section 01 12 16 | See Section 01 12 16 |

Agenda

1. Palo Alto RWQCP Factoids
2. Project Drivers
3. Process Selection
4. Construction Update
5. Project Team, Costs, and Timeline

Temporary Bypass System

3+1 Temporary Bypass
Pumping System




New Overhead Pipe Rack

New aeration piping

New Pipe Rack

Temporary Bypass
Pipe





New aeration
piping

New Serpentine
Wall, Typ

New
columns/beams

Temporary Blowers



Agenda

1. Palo Alto RWQCP Factoids
2. Project Drivers
3. Process Selection
4. Construction Update
5. Project Team, Costs, and Timeline

Project Team, Costs, & Financing

| | |
|---------------------------|----------------------------------|
| Design | Brown and Caldwell |
| Contractor | Anderson Pacific |
| Construction Manager | Carollo Engineers |
| Total Project Cost | \$193M |
| Financing | SRF Loan with 0.8% interest rate |

Project Timeline

| Step | Timing |
|-----------------------|---------|
| Design completion | Q3 2022 |
| Bidding / Award | Q4 2022 |
| Start Construction | Q1 2023 |
| Complete Construction | Q2 2028 |

Key Takeaways

- MABR is a great technology for intensification retrofits
- Relatively easy phasing of MABR cassettes gives flexibility
- Dry weather capacity may drive the design, not always PWWF
- Plan next expansion before building



Thank you.

Questions?

